

Details Specification for Renovation Class Rooms : L-2, L , J & Computer Room at old Building, at V.C.F.W.

Civil work :

Sl.No	Description	Qty	Rate	Amount
1.	ROOM : L-2			
	a) Dismantling loose & damaged under roof concrete surface, plaster etc placing in position exact reinforcement with Sika Rust-proof chemical including 6 mm stone chips , sand and cement (3:2:1) concrete mortar and new plaster 1: 4 mortar with Sika latex treatment . the work to be executed with proper care following specification and guide lines.	15 sq m		
	b) Applying 2 coats of Acrylic Distemper with 2 coats of acrylic primer ICI make , after necessary surface preparation	100 sq m		
	c) Synthetic Enamel painting (2 coats) over a coat of wood / steel primer, after necessary surfacing (door, window, grill etc)	10 sq m		
	d) Polishing of wooden student benches	10 each		
2.	ROOM : L			
	a) Dismantling loose..... guide lines.	25 sq m		
	b) Applying 2 coats Acrylic Distemper..... surface preparation.	130 sq m		
	c) Synthetic Enamel paint.....(.....etc)	25 sq m		
	d) Polishing of Benches.....	20 each		
3.	Room: J			
	a) Dismantling loose guide lines	10 sq m		
	b) Applying 2 coats acrylic distemper..... surface preparation	160 sq m		
	c) Synthetic enamel paint..... etc.	40 sq m		
	d) Polishing of Benches	30 each		
			TOTAL Rs	